



TENORM DECOMMISSIONING Refresher Course

SYLLABUS

Assumes the student has completed the 4-hour TENORM training.

PRESENTED BY:

Applied Environmental Consulting, Inc.

Summary of Tasks to Decommission a Site Contaminated with TENORM

DECOMMISSIONING PHASES

Phase I

- Notify regulatory authorities
- Submit decommissioning plan
- Obtain approval

Phase II

- Perform Scoping Survey
- Establish “Footprint” and background
- Remove contaminated items
- Perform post-remediation survey with metrics
- Perform sampling

Phase III

- Write report
- Complete on-site survey by regulator
- Perform additional remediation (as necessary)
- Obtain approval

INTRODUCES MARSSIM (Federal Guideline)

HOW TO ESTABLISH THE “FOOTPRINT” AND BACKGROUND

SPOT REMEDIATION REMEDIAL ACTIONS

TRAINING FOR WORKERS AND CONTRACTORS

RIGHT-TO-KNOW

RECOMMENDED PPE



RECORD KEEPING AND FORMS USED

VISITOR LOG

WASTE MANAGEMENT

TRANSPORTING TENORM AND SHIPPING OUT-OF-STATE

LICENSE TERMINATION REQUIREMENTS